BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED SCHEDULE –'B'

Name of Work:-Construction of RCC drain at Attur layout and surrounding area in ward no 03

Sl	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no143, PWD SR 2018-19)	Cum	353.70	137.80	Rupees One Hundred Thirty Seven and Paise Eighty Only
2	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/ kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no136,PWD SR 2018-19)	Cum	353.70	60.42	Rupees Sixty and Paise Forty Two Only
3	KSRRB M2100 PCC 1 KSRRB M2100-10. Plain cement concrete M10 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days complete as per specifications MORTH Specification No. 2100 (P No. 222/27.18)	Cum	70.74	5421.90	Rupees Five Thousand Four Hundred Twenty One and Paise Ninety Only
4	Providing laying palin / reinforced cement concrete for Side Drain using M20 normal mix concrete with OPC cement at 300kgs with 20 mm and down size granite metal coarse aggregates @0.69cum and fine aggregates @machine mixed, Well compacted for wall and bottom including centering shuttering Cost of material HOM of machinery curing etc excluding cost of steel as per MORTH Specification No. 1500,1700,2200 walls & bottomof thicknes 15(Page. 271 / Item.No. 37.59.2)	Cum	141.48	7070.20	Rupees Seven Thousand Seventy and Paise Twenty Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Yelahanka Division

	Description	Unit	Approved Qty	Approved Rate Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
5	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr2018-19,p.no18,s.no4.46)	Tonne,s	9.20	75809.08	Rupees Seventy Five Thousand Eight Hundred Nine and Paise Eight Only
6	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	471.60	2700.00	Rupees Two Thousand Seven Hundred Only

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064